ADDENDUM #1

Issued: April 1, 2026

Pinecrest Elementary School Roof Replacement, Project No. 2026-07

This addendum is part of the Bid Documents. Acknowledge this addendum on the Bid Form.

1. Section 07 52 00, Article 2.2: Roof membrane thickness is changed from 60 mils to 80 mils.
2. Drawing A-201: Add two overflow scuppers at the north parapet as shown on the attached sketch SK-1.

The bid date and time are not changed by this addendum.